




**SINGLE DUCT TERMINAL UNIT
ACCESSORY • DISCHARGE SOUND ATTENUATOR
MODELS: AT303 AND AT305**

Accessories:

Accessories ordered as separate models.

AT Discharge Sound Attenuator (loose)



- 22 ga. (0.86) galvanized steel construction.
 - Shipped loose for field attachment.
 - Slip and drive connection.
 - 3/4" (14) dual density fiberglass insulation, exposed edges coated to prevent erosion as standard.
- AT303** 3' (916) Long - Standard.
 - AT305** 5' (1524) Long - Optional.
 - Special Features: _____

Dimensional Data

Unit Size	W	H	AD
4, 5, 6	10 (254)	10 (254)	12 (305)
7, 8	12 (305)	12 1/2 (318)	12 (305)
9, 10	14 (356)	12 1/2 (318)	12 (305)
12	18 (457)	12 1/2 (318)	12 (305)
14	24 (610)	12 1/2 (318)	12 (305)
16	28 (711)	12 1/2 (318)	12 (305)
24 x 16	38 (965)	18 (457)	12 (305)

Options:

- Steri-Liner.
- Fiber-Free Liner.
- Solid Metal Liner.
- 1" (25) Fiberglass Liner.
- 2" (51) Fiberglass Liner.
- Perforated Metal Liner.
- Steri-Liner with Perforated Liner.
- Access Door
 - Sizes 4 to 12 : 8" x 5" (203 x 127) Oval;
 - Sizes 14 to 24 x 16: 12" x 6" (305 x 152) Oval.
- Special Features: _____

Note: Select Insulation to match VAV terminal.

SCHEDULE TYPE:	Dimensions are in inches (mm)			
PROJECT:				
ENGINEER:	DATE	B SERIES	SUPERSEDES	DRAWING NO.
CONTRACTOR:	3 - 30 - 17	3000	3 - 21 - 13	30AT